BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of the Work : Construction of Cement Concrete Drains at R.R. School Main Road and Cross Roads in Ward No. 10, (Doddabommasnadra) Vidyaranyapura Sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	409.95	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 Page No. 150 / Item No. 19.2/ PWD SR 2012-13	Cum	81.00	
2	208.23	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, corse aggregates @ 0.85 cum and fine aggregtes @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Page No. 12 /Item No. 4.3 PWD SR - 2012-13	Cum	3884.76	
3	787.20	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No.17 / Item No. 4.31 PWD SR - 2012-13	Sqm	244.08	
4	129.42	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.6 Page No. 13/ ITem No. 4.11 PWD SR - 2012-13	Cum	5239.08	
5	77.65	KSRB 4.9.1: Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19/ Item No. 4.45 PWD SR 2012-13	Qtl	7835.40	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
6	113.50	KSRRB M2600-3: Providing & fixing 20 mm thick compressible fibre board in expansion joint complete as per drawing & technical specification complete as per specifications, MORTH specification No. 2605, No. 248 Item No. 31.3 PWD SR 2012-13	M	132.84	
7	109.30	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggregares @ 0.43 cum with superplastisiser @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2, No. 12/ Item No. 4.5/ PWD SR 2012-13	Cum	4937.76	
8	1093.00	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratiry, Power Floater, blade and disc etc., with all lead and lift No. 187 / Item No. 22.7/ PWD SR 2012-13	Sqm	86.40	
9	409.95	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum	72.71	

Signture of the Contractor

Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL BBMP, Bangalore

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಈರದು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....( )
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Bangalore 92